## **NEW EQUIPMENT**

Mark For	Qty	Model Number	Description
RTU-1 Permanent Guidance	1	50VT-C365	Nominal 3 Ton Small Package HP RTU, 208-230/3/60V Field Installed:  Outside Air Intake Hood
(Existing Unit: B2HZ036A)			
RTU-2 Girls Locker (Existing Unit:	1	48VLUE360603-TP	Nominal 3 Ton Small Package G/E RTU, 208-230/1/60V  Ultra Low Nox  60,000 BTU/HR  Tin-Plated Indoor Coil Hairpin  Heat Exchanger (Standard)
PGD336)			Field Installed:  Outside Air Intake Hood
RTU-3 Permanent Nurse (Existing Unit: B1HA048)	1	50VT-C485	Nominal 4 Ton Small Package HP RTU, 208-230/3/60V Field Installed:  Outside Air Intake Hood  Curb Adapter-To Be Verified
RTU-4 Permanent Guidance (Existing Unit: PHN348)	1	50VT-C485	Nominal 4 Ton Small Package HP RTU, 208-230/3/60V Field Installed:  Outside Air Intake Hood
RTU-5  Boys Locker Office  (Existing Unit: PGD360)	1	48VLUE600903-TP	Nominal 5 Ton Small Package G/E RTU, 208-230/1/60V  Ultra Low Nox 90,000 BTU/HR Tin-Plated Indoor Coil Hairpin Heat Exchanger (Standard) Field Installed: Horizontal Economizer

DTU			No. 1 - 1 40 T - 110 DTU 000 000 (2/20)
RTU-6 Permanent 76 (Existing Unit: BP12C00)	1	50FCQM12A2A5-0A0A0	Nominal 10 Ton HP RTU, 208-230/3/60V  Single Circuit 2 Stage Cooling Standard Packaging Dir Drive-EcoBlue-Med Static Al/Cu - Al/Cu Electro-Mechanical Ctl
Di 12000)			Field Installed:  Curb Adapter – To Be Verified  Vertical Economizer
RTU-7 Permanent Lion Center (Existing Unit: DH180N)	1	48FCDM16A2A5-0A0A0	Nominal 15 Ton G/E RTU, 208-230/3/60V  Low Gas heat SIngle Circuit 2 Stage Cooling Standard Packaging Dir Drive-EcoBlue-Med Static Al/Cu - Al/Cu Electro-Mechanical Ctl Field Installed: Horizontal Economizer
RTU-8 New P-Building (Existing Unit: 48HJD014)	1	50FCQM14A2A6-0A0A0	Nominal 12.5 Ton HP RTU, 460/3/60V  SIngle Circuit 2 Stage Cooling Standard Packaging Dir Drive-EcoBlue-Med Static Al/Cu - Al/Cu Electro-Mechanical Ctl Field Installed: Curb Adapter – To Be Verified Vertical Economizer
ARTU-9 P Permanent P-Building (Existing Unit: 50AK- 025NN)	1	50A7-025ANS241EE	Nominal 25 Ton Cooling Only Applied RTU, 380/3/60V  VAV Vertical with Green Speed Intelligence  No Electric Heat  Ultra-Low Leak Economizer  No Convenience Outlet  "Precoated Al/Cu Condenser, Al/Cu Evaporator with Hot Gas Bypass"  Galvanized Drain Pan  2-inch Filter Track  Line Voltage Terminal Block  No Exhaust  10 Hp Supply fan motor with Variable Frequency Drive (VFD) without VFD Bypass  Controls Expansion Module (CEM) with Phase Monitor  Standard Ambient  Direct Fit – No Curb Adapter Required  Warranty:  Start Up  First Year Labor
CU-1,2 VP & Attendance (Existing Units: E1RA036)	2	25HCE436AP06	Nominal 3 Ton Split Heat Pump Condenser, 460-3-60V
FC-1,2	2	FB4CNP036L00	Nominal 3 Ton Fan Coil, 208/230-1-60V
CU-3 Girl's Dance (Existing Units: N2H360)	1	25HCE460AP03	Nominal 5 Ton Split Condenser, 208/230-1-60V
FC-3	1	FB4CNP061L00	Nominal 5 Ton Fan Coil, 208/230-1-60V
CU-4 P-Building 3 Ton Split	1	24AHA436A003	Nominal 3 Ton Split A/C Condenser, 208/230-1-60V
EC-4	1	CAPMP3617ALA	Nominal 3 Ton Cased Multi-Poise Evaporator Coil
Furnace	1	58SU0A040E1712	4-WAY 80% AFUE 40k Btuh Ultra Low NOx Furnace, 115V