

ARCHITECTURE ENGINEERING PLANNING INTERIORS
1650 Spruce Street. Suite 300

Riverside, CA 92507 T: 951.682.0457

South El Monte High School Modernization

El Monte Unified High School District

Addendum 4

Project Reference: South El Monte High School Modernization Date: 11/21/2022

DLR Group Project 75-20225-00 DSA Application # 03 – 1222081

Submitted By: Hernan Chavez, Project Manager

To: Prospective Bidders

Attention: Cost Estimator

This Addendum forms a part of the Contract Documents and modifies the original documents approved by the Division of the Sate Architect (DSA) on September 21, 2022. The following changes, deletions, additions and/or alterations in, on and to the documents shall apply to proposals made for the execution of the various parts of the work affected thereby. All clouded revisions on any attached Addendum documents shall be fully made a part of the contract documents and compliment what is being listed in the Addendum narrative.

Careful note of this addendum shall be taken by all parties of interest so that the proper allowance may be made in all computations, estimates, and contracts, and all trades affected shall be fully advised in the performance of the work which will be required of them.

Acknowledge receipt of this addendum in the space provided on the Bid Form. Failure to do so may subject the bidder to disqualification.

ITEM DESCRIPTION:

4.0 Pre-Bid RFI Log – Assignment Narrative

Bid Package 1 - General Construction

* Responsible for all landscape demolition.

Bid Package 4 - Roofing and Sheet Metal

- Per spec section 07 54 30, B, 10, apply acrylic coating. Refer spec section 07 54 30 subsection 2.2 for bases of design manufacturer information.
- Refer to detail 26/A10.1 for roof plan tags at buildings K and M.
- Install roof pipe flashings and counterflashings provided by bid package 13 contractor.
- ❖ Install roof flashing for plumbing penetrations provided by bid package 12 contractor.

Bid Package 5 - Landscape and Irrigation

- Provide interim landscape maintenance through the completion of the project.
- Perform landscaping work in phases, per Project Milestone Schedule provided.
 - Assume multiple mobilizations and assume work will be performed over the Summer and while school is in session.
 - Use delineators to avoid disturbing active campus.
- Refer to Pre-Bid RFI 19 response for SCH 40 Pipe Chart.

Bid Package 11 - Electrical and Low Voltage

- Use existing MDF and IDFs.
- Include Structure Cablings, Audio Visual, and Security in order to submit your bid.
- Provide and install Security Card Reader(s) per revised spec section 23 09 00.
- Provide (2) Category 6 cables for each WAP location per Electrical Symbols List on sheet E0.02.
- There are no specific part numbers required for the Berk-Tek/Leviton solution, therefore provide and install per contract documents.
- Provide labor and materials for any electrical modifications to the existing exhaust fans. Other modifications to existing exhaust fans are the responsibility of the bid package 13 contractor.
- ❖ Blue cable is acceptable if the purple/violet colored Category 6 cable is not available.
- Provide door contacts as part of the Intrusion Detection System.
- No CCTV required under this scope.
- Rework rack to support scope of work as required.
- Wireless Access Points listed in spec section 27 10 001 subsection 2.15 are Owner Furnish, Contractor Installed (OFCI).
- No fiber or copper backbone is required for the scope of work.

Bid Package 12 - Plumbing and Site Utilities

Furnish roof flashing for plumbing penetrations.

Bid Package 13 - HVAC

- Reuse existing Carrier I Vu controls to matching existing controls system.
- ❖ Furnish roof pipe flashings and counterflashing's required for own work.
- ❖ Provide labor and materials for any adjustments to the existing exhaust fans. Electrical modifications will be responsibility of the bid package 11 contractor.

4.1 Pre-Bid RFI Log

See attached Pre-Bid RFI log with responses as enclosed in Addendum 4.

Sincerely, Jesse Miller, AIA, Assoc. DBIA DLR Group

Cc:

Norma Macias, Director of Facilities, Maintenance, Operations & Transportation – El Monte Union High School District Mike Arnold - Erickson Hall Jorge Cruz – Erickson Hall Cecilia Galaviz – Erickson Hall

RFI#	SUBJECT	QUESTIONS	OFFICIAL RESPONSES	RESPONSIBLE BID PACKAGE	CHANGES PER ADDENDA
PB-1	Siemens Controls	From: Jesse Del Rio - Next Level EMS 1.5 APPROVED CONTROL SYSTEM CONTRACTORS AND MANUFACTURERS A. The contractor shall use the Siemens Apogee System. No other manufacturer shall be accepted. This item is being sole sourced per Public Contract Code Section 3400, subdivision (b) (2) to match equipment in use at the project either completed or in the course of completion.B. Siemens Industry, Inc. — (714) 227-5140 — Doug PittardC. No substitutions shall be accepted. No known equal. Clarification:Next Level EMS is an Authorized Siemens Dealer. We are authorized to install Desigo CC which is the latest software Siemens has available, both Siemens Branch and Next Level are authorized to install Siemens Desigo CC. Next Level can even integrate into legacy Siemens Insight if thats a requirement. By allowing Next Leve to provide Siemens controls this would allow competitive bidding per public contracting code. Please confirm if Next Level EMS is approved to bid this project utilizing Siemens controls.	Controls shall be Carrier I Vu to match existing control system. Plans show existing controls to be reused. Tony Ramirez DCGA Engineers	13 - HVAC	Scope Clarigication
PB-2	Project Schedule	From: Allison Grijalva (Pierre Landscape, Inc) Will a project schedule be provided?	Project Milestone Schedule was provided via Addendum 1 on October 26, 2022. This document can be accessed via the district's		Schedule Clarification
PB-4	Bid Package No. 5 (Landscaping & Irrigation) Estimated Value	From: Tiffany Trujillo - KASA Construction, Inc Requesting Estimated Value of project by Bid Packages. Specifically Bid Package No. 5 - Landscaping & Irrigation. This is needed for Bonding purposes.	website: https://www.emuhsd.org/Page/146. There are no estimated values for respective bid packages. The only estimated value provided is the Project Cost Estimate of \$24,000,000.00.		No Change
PB-3	Project Labor Agreement	From: Tiffany Trujillo - KASA Construction, Inc Please confirm whether this project is subject to a PLA (Project Labor Agreement), a PSA (Project Stabilization Agreement), a CBA (Collective Bargaining Agreement), a CWA (Community Workforce Agreement), or anything of that nature?	This project is not subject to any labor agreements or anything of that nature.		No Change
PB-5	Landscape Maintenance Service per Bid Package Inclusions	From: Alex Yuchongtian - Pierre Landscape, Inc Bid package 05 inclusion #23 notes that the maintenance service period does not start until date of Certified Completion is established by owner. Given that the work is completed in phases, shall we anticipated that the start of landscape maintenance and certified completion by owner will be granted upon completion of each phase. Or if Landscape maintenance start date will only be granted until completion of the project in its entirety, with the projected completion date of April 2024. Therefore, warranting interim maintenance requirements.	Landscape maintenance start date will be granted until completion of project in its entirety; therefore, Contractor is to provide interim maintenance through the completion of the project.	05 - Landscaping & Irrigation	Maintenance Scope Clarification
PB-6	Sitework Working Hours	From: Alex Yuchongtian - Pierre Landscape, Inc Please confirm that sitework may be performed and coordinated during school hours. Note that crew sizes will be properly managed to accommodate day work only, delineators will be provided, and care will be taken to not disturb ongoing campus activities.	Landscaping work will be performed in phases. Assume multiple mobilizations and assume work will be performed over summer and while school is in session. Delineators will be required to not disturb active campus.		Scope Clarification
PB-7	Landscape Demo Clarification	From: Alex Yuchongtian - Pierre Landscape, Inc Refer to Partial Demolition Plans C1.1 – C1.5. There exist demolition notes in the legend indicating tree and landscape demo, though they are not specifically listed or illustrated on the plans. Please advise and confirm that the demolition subcontractor and Bid package 01 is to provide demolition of all landscape and sod, clearing of trees and shrubs, and rough grading of all areas intended to be relandscaped. See diagram below superimposed landscape area on top of the demo key map. Please advise.		01 - General Construction	Scope Clarification

South El Monte High School Modernization | PRE-Bid RFI LOG Addendum 4 11/21/2022

PB-8 Electrical/Low Voltage Clarifications	From: Richard Hernandez - Federal Technology Solutions, Inc 1. Can cabinet/rack elevation details and locations for each IDF and MDF be provided? 2. Is OSP backbone cabling required between the MDF & IDF buildings (i.e. Fiber, Copper.)? 3. CCTV locations are not depicted on the drawings. Can this be provided? 4. Does a Structured Cabling, Audio Visual, and Security all have to be provided in order to submit our proposal? 5. Please provide Security Card Reader manufacturer and cable type? 6. Please clarify an open triangle on the drawings, with no number associated with it will receive (1) Category 6 cable at the outlet location. 7. Are all ceiling spaces considered to be a plenum rated environment? 8. How many Category 6 cables are to be provided for each WAP location? 9. Are there specific part numbers required for the Berk-Tek/Leviton solution?	MDF and IDF's are existing.2) No, MDF and IDF's are existing. 3) No new CCTV locations required.4) Yes.5) Information provided as part of Addendum.6) Yes.7) No, most areas are ducted return.8) (2) per electrical symbols list on E0.02.9) No. DCGA EngineersC. Villalobos11/21/2022	11 - Electrical and Low Voltage	Scope Clarification
PB-9 Coating Clarification	From: Rick Delaloza - AME Builders, Inc Spec Section 07 54 30 - B - 10 states to "Apply acrylic to asphalt primer over existing surface prior to any repairs or acrylic roof coating. Repair any voids, tears or deficiencies with 3-course treatment of Acrylic Flashing with Polyester Reinforcement. Install 3 gallons of Acrylic Elastomeric Reflective Coating (2 passes at 1.5 gallons per 100 square foot each) up and over the existing parapet wall." What coating is being referred to? Where are the specifications for it? And what bid package is responsible for it?	Bid Package #04 is responsible for this coating. , Refer to Specification section 07 54 30 Subsection 2.2 for basis of design manufacturer information. Hernan ChavezDLR Group 11/7/2022	04 - Roofing and Sheet Metal	Scope Clarification
PB-10 Architectural Symbol Clarification	From: Rick Delaloza - AME Builders, Inc What does RT-2(B) represent? It is on the plans twice at both lower roof sections at the North and South parts of the roof.	Roof plan tag RT-2 (B) represents roof type A or B as outlined on detail 26/A10.1. Roof tags used will be RT-2 (A) or (B) on buildings K and M. Type (C) will be revised to read type (B) in upcoming Addendum 2. All other buildings will use RT-2 (A) for single ply over wood deck. See attached roof detail 26/A10.1 for your reference. Hernan ChavezDLR Group11/7/2022	04 - Roofing and Sheet Metal	Scope Clarificatiom
PB-11 Bid Package #13 Clarifications	From: Rick Delaloza - AME Builders, Inc Please clarify if bid package #13 will supply and install or just supply all roof pipe flashing for all HVAC pipe penetrations for bid packages #4 to install? Same question for the sheet metal counterflashing at mechanical units.	Bid package #13 is responsible for roof pipe flashings and counterflashing's required for own HVAC work. Bid package #4 is responsible for installing these metal flashings.	04 - Roofing and Sheet Metal / 13 - HVAC	Scope Clarificatiom
PB-12 Bid Package #12 Clarification	From: Rick Delaloza - AME Builders, Inc Please clarify if bid package #12 will provide all roof flashings for the plumbing penetrations and install or provide to bid package #4 to install.	Bid package #12 will furnish the roof flashing for plumbing penetrations and Bid package #4 will be responsible to install. JC	04 - Roofing and Sheet Metal / 12 - Plumbing & Site Utilities	Scope Clarification
PB-13 Existing Exhaust Fans	From: Rick Delaloza - AME Builders, Inc What does 2301 represent in reference to the existing exhaust fans? And what bid package will be responsible for raising the ones that are less than 8" high?	Any adjustments to the existing exhaust fans will be the responsibility of the HVAC bid package contractor. Any electrical modifications are the responsibility of the electrical bid package contractor., Keynote 23 01 will state the following: "New Rooftop Exhaust Fan, See M DWGS." The keynote will be populated on the roof plans in upcoming Addendum 2. Hernan ChavezDLR Group11/7/2022	11 - Electrical and Low Voltage / 13 - HVAC	Scope Clarification
PB-14 Existing Conditions - Roof	From: Rick Delaloza - AME Builders, Inc Since we were not able to walk all roofs, how will we verify existing conditions? Will another roof walk be scheduled?	No additional walks are planned at this time. JC	04 - Roofing and Sheet Metal	Scope Clarification

South El Monte High School Modernization | PRE-Bid RFI LOG Addendum 4 11/21/2022

PB-15 Division 12 Scope Clarifications	From: Doug Martin - Core Contracting, Inc BP 03 has the following four spec sections to be included and is duplicated to be included in BP 01. 12 35 53.19 12 35 53.25 12 36 23.13 and 12 36 61.16 Which BP should have these spec sections?	The following are listed on both BP 1 and 3. 12 35 53.19 - Wood Lab Casework12 35 53.25 - Adaptable Lab Bench12 36 23.13 - Plastic Lam Clad Countertops12 36 61.16 - Solid Surfacing Countertops These sections should be picked up by BP 3 Rough Carpentry and Casework and deleted from BP 1 GC. -JC	03 - Rough Carpentry and Architectural Woodwork	Scope Deleted from BP 01 and Added to BP 03
PB-16 Low Voltage Clarifications	From: Richard Hernandez - Federal Technology Solutions, Inc. 1. Spec Section 27 10 01-33 Intercom-Public Address System-Clock System 2.16 F. depicts Atlas part numbers and a Cisco PoE Switch that are obsolete. Can you provide replacement for these items? 2. Due to availability can the the Category 6 [purple/violet] in Spec Section 2.16 F. be replaced with a Blue cable? 3. Can you please provide cabinet sizes with part number for each IDF/MDF? 4. Are we providing vertical or horizontal PDU's for the cabinets or racks in the MDF/IDF? If yes, please provide quantity and part numbers. 5. Can you provide cabinet sizes for the Intercom-Public Address-Clock System equipment?	1) PA system is an existing Telecenter and will be extended/reworked for scope. 2) Blue cable is acceptable. 3) MDF and IDF's are existing. 4) No, MDF and IDF's are existing. 5) PA system is an existing Telecenter and will be extended/reworked for scope. DCGA Engineers C. Villalobos 11/21/2022	11 - Electrical and Low Voltage	Scope Clarification
PB-17 AV Systems Scope	From: Valerie Crellin - Avidex 274116 - Spec states that the Cafetorium is all that's being installed. There is also nothing in drawings showing any classrooms AV systems. Please confirm that AV install is for Cafetorium only? If classrooms are included in bid phase, please provide detailed drawings/parts/SOW. Spec/plans - add 1 shows different phases. Is bid for all or for specific phases?	As part of this scope of work only the AV system in the Cafetorium is required. Classrooms shallhave infrastructure for future AV system.All phases shall be included.DCGA EngineersC.	11 - Electrical and Low Voltage	Scope Clarification

South El Monte High School Modernization | PRE-Bid RFI LOG Addendum 4 11/21/2022

PB-18	AV Clarifications	From: Valerie Crellin - Avidex	1. Specification provided for access controls in the project manual.	11 - Electrical and	Scope Clarification
	7.17 Glaimballono	Training Grammi Arrigan	Specification provided for access controls in the project	Low Voltage	Coope Claimeanen
			manual.	zon romago	
		87100 - 3.7 - Door schedule notes AD-400 lockets but Div 28 security contractor	Door contacts are required.		
		however none exists. Please provide Div 28 specification with regard to door access	CCTV not required under this scope.		
		control scope.	5. IDF/MDF existing to remain. Rework of rack required to support		
		control scope.	scope of work.		
		Per Comm Sheets - Card Readers are noted on plans however no specification for	6. No fiber or copper backbone required for the scope of work.		
		Access control system is supplied. Please provide info for Access Systems.	7. Wireless access points are OFCI.		
			8. PA is existing Telecenter System.		
		Per E Symbol List - Intrusion Detection devices are noted in key but no spec or devices	9. All phases.		
		noted on plans. Confirm intrusion is not a requirement.	10. Confirmed.		
		·	11. (E) MDF located in B109A.		
		Spec 271001 2.17 Closed Circuit Television (CCTV) System provides details. However,	12. (E) IDF located in C122.		
		the plans do not reflect any CCTV requirements. Will there be any CCTV scope required	13. (E) IDF locations for BLDG D and E are located in exterior		
		on this project? If yes, please provide plans showing locations and mounting details.	enclosures adjacent to Building to BLDG F.		
			14. (E) IDF located in K123.		
		271001 - Plans/Specs - Please confirm that all IDF/MDF's are Existing and there are no			
		requirements for racks and IDF/MDF room buildouts and materials listed in spec 271001			
		should be removed from this scope of work.	17. IDF/MDF existing to remain. Rework of rack required to support		
		'	scope of work.		
		271001 - Plans/Specs - There is no site plan or riser diagram provided showing any	18. No fiber or copper backbone required for the scope of work.		
		Fiber/Copper backbone requirements. Please confirm that all the backbone is existing			
		and Fiber/Copper sections of the spec 271001 should be removed from this scope of	Chris Villalobos		
		work.	DCGA Engineers		
			11/21/2022		
		27100 - Plans/Specs - Please confirm the Wireless Access Points listed on Spec			
		271001 2.15 are to be OFCI or CFCI.			
	Irrigational Lateral and Mainline	From: Alex Yuchongtian - Pierre Landscape		05 - Landscaping and	Scope Clarification
	Sizing		Sizes.Craig DuncanSilver Bar Studio16November2022PIPE	Irrigation	
		Refer to L1.01 – L1.03. Irrigation plans do not indicate lateral line and mainline sizing.	SIZING CHART - SCH. 40FLOW/GPM PIPE SIZE7-12 1"13-22 1-1		
		Please advise.	/ 4"23-30 1-1 / 2"31-50 2"		
PB-20	Bid Package #01 Note Clarification	From: Steve Arlotti - KYA Services LLC	This line item should reference "Division 01 General		Spec Section Correction
			Requirements" in lieu of "section 00 10 00 General Requirements".		
		1. In Bid Package 01 page 5 item #20 "this bid package contractor is responsible for all	This change will be reflected in a forthcoming Addendum.		
		items included in the CM Supplemental Specifications including, and all other			
		requirements as specified in section 00 10 00 General Requirements" I do not see this			
		section, please advise where I can find this spec.			
PB-21	Aurora Mobile Substitution Request	From: Octavio Trejo - Yamada Enterprises	Proposed substitution request is not acceptable.	01 - General	No change
				Construction	
		See attached Substitution Request. Please advise if the alternate submitted for the	Hernan Chavez		
		mobile shelving storage is acceptable.	DLR Group 11/21/22		